BRUHAT BENGALURU MAHANAGARA PALIKE, DASARAHALLI ZONE,
M.E.I.LAYOUT, BAGALAGUNTE, HESARAGHATTA MAIN ROAD, BANGALORE-560 073

No: EE/DD/WO/ 402 /19-20

Office of the Executive Engineer,
Dasarahalli Division,
Dated: 27/09/19

Work Order

To
Sri. Jayanna
889, 1st Cross
Munneshwara Nagara
Banagalore-73

Sir,

Name of Work:	Construction of CC drain and providing CC slab at Balaji scan center to park in Bagalagunte ward no 14		
Est Cost:	20.00	Lakhs	Indent No:34722
Job Code:	014-20-000007		PCode-1771
Administrative Approval:	EE/DD/AS/115/19-20, Dt:17.06.2019		
Technical Sanction:	EE/DD/TS/46/18-19, Dt:30.01.2019		
Tender Notification No& Date:	BBMP/EE/DD/Ten/15/2018-19, Dt:04.02.2019		

-:-:-

By Virtue of having Executed Agreement and the same has been accepted by the Chief Engineer/Executive Engineer for the Work mentioned in reference, for the tender price of **Rs. 18,27,531.00** Rupees (Eighteen Lakhs Twenty Seven Thousand Five Hundred Thirty One only) (Which is-6.95 % Above to SR-2018-19 + 12% GST Additional Add).You are hereby instructed to proceed to execution of the said work in accordance with the contract documents. Consultation with the Concerned Ward Assistant Executive Engineer, and complete the work as per agreement within 90 days from the date of issue of this letter.

Yours faithfully,

Executive Engineer,
Dasarahalli Division,
BBMP, Bengaluru.

Copy to:

1. Addl.commissioner, Dasarahalli Zone, for kind information.
2. Chief Engineer. Dasarahalli Zone, for kind information.
3. E.E., Q.C. for Kind information.
4. A.E.E. (Shettyhalli / Dasarahalli / P.I.A / Hegganahalli) Sub Division, A copy of Accepted Rate list is enclosed for your information and guidance.
5. Office copy

Scanned by CamScanner

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer

SCHEDULE-B

NAME OF WORK: Construction of CC drain & Providing CC slab at Balaji scan center to Park in Bagalagunte Ward No.14

Sl. No	Description of work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	KSRRB 300 - works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	60.75	147.3771	
2	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	Cum	27.60	2140.36896	
3	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.	Cum	79.65	5798.72205	
4	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification	Cum	81.90	7561.5789	
5	Supplying, fitting and placing TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specificationsMORTH Specification	Tonne	4.91	77353.7051	

Scanned by CamScanner

6	Supplying and fixing precast rainforced concee slab .23cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Cum	124.50	2361.456	
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	60.75	74.6511	

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Scanned by CamScanner